

Experience on spoke cavity development and future plan at IHEP

Feisi He

On behalf of colleagues in IHEP SRF group Institute of High Energy Physics (IHEP)




Outline


- Introduction to CADS linac
- Development of spoke cavities
- Cryomodule commissioning and operation
- Future plans



Introduction to the CADS linac



- IHEP is in charge of the injector-I linac, and the CM4 of the main linac
- Spoke012/021/040 cavities have been developed at IHEP at 162.5 MHz HWR010




CADS main linac at IMP

HEBT




Spoke012 cavity

14 cavities in 2 CM. Beam commissioned with 2mA CW proton from 3.2MeV to 10MeV



Layout of ADS injector I

	Spoke 012
β_0	0.14
Aperture-mm	35
Ep/Eacc	5.0
Bp/Eacc-	6.9
$mT/(MV/m)^2$	
G-Ω	60
R/Q-Ω	150
df/dp [Hz/mbar]	-40
df/dp [Hz/mbar]	-130~-83
(measured)	
LFD	-13
[Hz/(MV/m)2]	




May



Spoke021 cavity

 6 cavities in one CM. developed in IHEP, Assembled in IMP. Beam commissioning is on going.



	Spoke 021
β_0	0.24
Aperture-mm	40
Ep/Eacc	4.4
Bp/Eacc-	9.4
$mT/(MV/m)^2$	
G-Ω	71
R/Q-Ω	191
df/dp [Hz/mbar]	-6
df/dp [Hz/mbar]	<-10
(measured)	





Spoke040 cavities

- It was proposed to use 72 Spoke 040 cavities in the future ADS linac
- Two type of Spoke040 cavities have been fabricated and exceeded design target in vertical test


	Spoke 040-1	Spoke 040-2
Freq. [MHz]	325	650
βο	0.46	0.40
Aperture [mm]	50	50
E _p /E _{acc}	3.9	3.6
B _p /E _{acc} [mT/(MV/m)]	9.2	8.8
Geometry factor [Ω]	104	91
R/Q [Ω]	265	246







Fabrication of IHEP spoke cavities



LHe vessel Single cavity test

Design


Fabrication

Post processing

Assembly

Certification from vendor Eye inspection

Material



Defect inspection and grinding before final EBW, size control, frequency

control

-

Quality control

Deep drawing, annealing, machining, frequency control, grinding, EBW







Post processing of Spoke cavities

 BCP in Ningxia OTIC; re-HPR and clean assembly in IHEP









Ultrasonic

BCP120 um

800C 2hr

BCP30 um

HPR

120C 48hr

Vertical test

Vessel weld

650C 3hr

BCP30 um


HPR


String assembly



VT results of the spoke012 cavities

- MP conditioned in 1 hour with variable coupler
- Eacc increased by 2 MV/m with better cooling
- 120C baking increases Q₀ by about 50-100%
- At 2K, Q0 is 6 times higher, Bp~125mT achieved.









Spoke021 testing results

- MP conditioned in 1 hour
- Design target consistently exceeded
- Bp of 120mT and Rres of 7nΩ achieved at 2K









Outline

- Introduction to CADS linac
- Development of spoke cavities
- Cryomodule commissioning and operation
 - Measurements on cryomodule
 - Problems and improvements
- Future plans




Injector-I commissioning

- 2015.1.13, TCM was installed in the tunnel
- 2015.1.26, TCM reached 2K
- 2015.4, TCM was commissioned, CM1 installation started
- 2015.8.1, CM1 was installed in the tunnel
- 2015.8.28, CM1 reached 2K
- 2015.9.11-11.20, CM1 was commissioned
- 2016.3.20, CM1 and CM2 were connected in the tunnel
- 2016.6-2017.1, CM1 and CM2 were commissioning













CM1&CM2 cooling down

- It takes about 5-6.5 days to reach 4K stable operation
- Measured df/dp is about -130Hz/mbar for CM1 cavities, and -83Hz/mbar for CM2 cavities; LFD is about -13Hz/(MV/m)2; Q0 is not measured yet.


Cavity_ID	1	2	3	4	5	6	7	8	9	10	11	12	13	14
df_4KvsRT [kHz]	546	523	540	462	509	557	496	408	428	511	323	572	519	553
df/dp [Hz/mbar]	-157	-129	-134	-150	-131	-119	-91	-66	-47	-96	-82	-75	-97	-119
LFD [kHz]	-14	-12	-11	-13	-12	-10		-13	-13	-9	-10	-12	-9	-16









Static heat load of the CM1






- The maximum temperature difference on thermal shields were less than 40K during cooling down
- Heat load of 30W measured by liquid level and mass flow rate agree in 7%
- LHe pressure stability was improved from ± 0.6 mbar (TCM) to ± 0.05 mbar (CM1)






Cavity conditioning

- Cavity conditioning at 4K typically takes 1-2 days
- Cavity was conditioned to 8MV/m before beam operation (FE for cav 1-4#, administrative for Cav5-14#)
- On beam operation of 10MeV mode, average cavity gradient is 6MV/m, i.e. Ep~27MV/m









Problem: high noise level

- Vibration was measured by accelerometer
- Microphonics was reduced by one magnitude, by removing the scroll pump from the cart.











Problem: too high df/dp

- Problem: way too huge df/dp (-130 than -40Hz/mbar)
- Mainly by deformation of beam pipe
- Solution: adding stiffeners to He vessel, and stronger TIG welding

Cavity_ID	1	2	3	4	5	6	7	8	9	10	11	12	13	14
df/dp [Hz/mbar]	-157	-129	-134	-150	-131	-119	-91	-66	-47	-96	-82	-75	-97	-119
LFD [kHz]	-14	-12	-11	-13	-12	-10		-13	-13	-9	-10	-12	-9	-16








Un-expected high df/dp on Spoke021

- Improved design for df/dp ~ 10Hz/mbar
- Unexpected high df/dp in production phase
- df/dp is extremely sensitive to the depth of one weldment, which was switched from EBW to TIG
- Re-weld with EBW solved the problem

df/dp [Hz/mbar]	Before	After		
021-5#	-60	0		
021-6#	-40	-13		
021-7#	-58	-12		
021-8#	-82	-9		
021-9#	-67	-15		
021-10#	-65	-11		


Weld depth[mm] (slide fit 0.2mm)	df/dp [Hz/mbar]				
5	-1.0				
4	-6. 5				
3	-16.2				
2	-32.7				
1	-64. 4				






Tuner issue


- Switch from pushing to pulling help reduce df/dp
- Severe backlash and overshoot possibly caused by gears and joints
- They were replaced from service port, which helped more or less







Tuner issue (2)



CM1-1 CM1-2 CM1-3 CM1-4 CM1-5 CM1-6 CM1-7 CM2-1 CM2-2 CM2-3 CM2-4 CM2-5 CM2-6 CM2-7

Oversho ot [Hz] 55 105 5200/ 1120/ 2995 215 500 155 117.5 35 0 102 123 104.5 139 27.5


May 22nd, 2017, FREIA visit, Uppsala, Sweden




Further improvement on CM4 tuner

- The tuner were re-designed to eliminate loose gears and joints.
- The overshoot was under-control







	CM4-1	CM4-2	CM4-3	CM4-4	CM4-5	CM4-6
Overshoot [Hz]	9	21		10	0	2




Outline

- Introduction to CADS linac
- Development of spoke cavities
- Cryomodule commissioning and operation
- Future plans



Future project: CIADS


- Approved by Chinese government in Dec. 2015
- Budget: >1.8B CNY
- In collaboration of IMP, IHEP, and many other institutes
- IHEP will continue spoke cavities R&D and production under the scope of CIADS project





Future project: HEPS


- High Energy Photon Source will be built in Beijing by IHEP from 2018 to 2024
- Budget: 4.8B CNY





Future project: CEPC

- Proposed by IHEP, pre-research in progress
- Circular electron-positron collider at 2 x 120GeV
- ~600 SRF cavities at 650MHz needed
- Operation specification: Q₀>2e10@E_{acc}=16MV/m
- VT specification: Q₀>4e10@E_{acc}=22MV/m



May 22nd, 2017, FREIA visit, Uppsala, Sweden



PAPS project for the future projects

 "Platform of Advanced Photon Source Technology R&D" project supported by Beijing Gov.

Budget: 500M RMB

Construction: 2017.5-2020.6

Consist of 7 systems:

SRF system

Cryogenic system

Magnet technology

- Beam test
- X-ray optics
- X-ray detection
- X-ray application








SRF facility to be built

- The SRF facility is part of the PAPS-RF system
- It will do post-processing, clean assembly, and all tests for mass production of cavities, couplers, and cryomodules.
 - Compatible of 166MHz, 500MHz, 650MHz, and 1.3GHz
 - 200-400 cavities (couplers) per year
 - ~20 cryomodules per year

Support R&D on new material


and new technology

- Total area of 4500 m²
- Cryogenic system:300W @ 2K





Layout of the SRF facility





ESS&IHEP possible collaborations

- Joint development in hardware/software/application for Spoke cavities testing.
- Joint development in hardware/software/application for Elliptical cavities testing.
- Short to middle term visit for the commissioning of the joint-developed hardware /software/applications.
- Knowledge and expertise exchange of Test stand setting up and operation.
- Data and information sharing.



Thanks for your attention!