

Cornell-BNL ERL Test Accelerator CBETA

Status & opportunities

Steve Peggs, Project Director,
for the CBETA collaboration

Thanks for material created by many people:

Cornell: Adam Bartnik, David Burke, John Dobbins, Rihc Gallagher, Colwyn Gulliford, Georg Hoffstaetter, Yulin Li, Peter Quigley, Karl Smolenski.

BNL: Scott Berg, Stephen Brooks, Khianne Jackson, George Mahler, Rob Michnoff, Steven Trabocchi, Dejan Trbojevic, Joe Tuozzolo.

Jefferson Lab: Steve Benson, Dave Douglas.

Oxford: Adam Steinberg.

SLAC: Chris Mayes (ex-Cornell).

Why an ERL? Why BNL+Cornell ?



- Synchrotron:** Repetitive acceleration, low repetition rate
high energy, low current, relatively large beam size.
- Storage ring:** Occasional fills, long-time storage.
Requires very low loss rates.
high energy, high current, relatively large beam size.
- Linac:** Single pass energy limited by the length.
Average_current*Energy limited by wall-plug power.
moderate energy, low current, small beam size.
- ERL:** Linear deceleration recaptures spent beam energy.
“No” wall-plug power limit on average beam current.
Very low loss rates + new accelerator physics regime !
moderate energy, high currents, small beam size.

A Possible Apparatus for Electron Clashing-Beam Experiments (*).

M. TIGNER

Laboratory of Nuclear Studies, Cornell University - Ithaca, N. Y.

(ricevuto il 2 Febbraio 1965)



Energy recovery needs **continuous waveform RF** fields

- **Normal** conducting high field cavities **waste energy**.
- **Superconducting** cavities **used** to have too **low fields**.


- 1934 Livingston: first non-Berkeley cyclotron (2 MeV p)
- 1949 Wilson: first stored beam in synchrotron (300 MeV e)
- 1954 Wilson: first strong focusing synchrotron (1.1 GeV e)
- 1979 Cornell Electron Storage Ring CESR (up to 8 GeV)
- 1990's World's highest luminosity for a decade

2017 CESR operation & upgrade
as light source CHESS

CESR as a storage/damping
ring test facility →

ERL prototyping facility (eg
for proposed FEL)

CBETA!




2015 DOE Nuclear Science Advisory Committee Long Range Plan Recommendation III

“We recommend a high-energy, high-luminosity polarized **Electron Ion Collider** as the highest priority for new facility construction following the completion of FRIB.”

New York State Energy R&D Agency (NYSERDA) contract

“Successful demonstration [of **CBETA**] will ensure that the **electric power requirements** of the eRHIC design are within acceptable limits, with respect to operating costs and reuse of existing power infrastructure at BNL.”


CBETA basics



Much equipment & infrastructure exists — 32 M\$

Major new equipment:

- 2 splitters (electromagnets & tables)
- Halbach (permanent) magnets in return arc
- Diagnostics, power supplies etc.



Circumference = 70.100 m

4 key technical features ...

1. 4 pass up, 4 pass down, energy recovery
2. Superconducting RF (1.3 GHz)
3. Very strong focusing single aperture optics
4. Halbach permanent magnets

... have been individually demonstrated elsewhere, but CBETA is first to put them all together.

The optics are unique in demonstrating no-symmetry adiabatic transitions from FFAG arc to straight.

These technologies could be used in a next generation EIC, e.g. eRHIC at BNL.

Very strong focusing return loop:

- Momentum aperture **factor of 4**
- **Precision, reproducibility, alignment** (production/installation).
- Stability of **magnetic fields in a radiation** environment.
- **Matching & correction** of 4 simultaneous **orbits & optics**
- Independent **path length** control for all orbits.

Multi-turn ERL operation:

- **Higher Order Mode** damping.
- **Beam Break Up** limits.
- **Low Level RF** control and microphonics.
- ERL **startup from low-power** beam.

Key Performance Parameters are 1-pass, with 4-pass capability fully installed.

Design parameters are stretch goals — with challenges / opportunities for **post-NYSERDA collaboration**

Parameter	Unit	KPP	Design
Electron beam energy	MeV		150
Electron bunch charge	pC		123
Gun current	mA	1	40
Bunch repetition rate (gun)	MHz		325
RF frequency	MHz	1300	1300
Injector energy	MeV		6
RF operation mode			CW
Number of ERL turns		1	4
Energy aperture of arc		2	4

BNL collaborate with Cornell University, to test & develop a 4 pass Energy Recovery Linac using a single aperture return loop with an energy acceptance factor of up to 4.

Relocate:


- Source gun with its laser system
- Injector Cryo-Module & Main Linac Cryomodule (MLC)
- High-power beam stop

Install:

- Return loop with a single aperture accepting 4 discrete energies
- Splitters to connect the arc to the MLC.

Commission & operate with 1 mA, increasing towards 40 mA.

Visible evolution



6-cavity


Main Linac Cryomodule (MLC)
in non-beam test location




Miscellaneous stuff
under a 30 ton crane


High voltage
source gun
~400 kV

Injection
CryoModule
6 MeV





Laser
table



Translation stages




Photocathode
“pucks”

MLC in place for beam






ILC, MLC, & diagnostic beamline



400 kV
cans

Injection
Cryomodule
ICM



Main Linac
Cryomodule

Diagnostic
beamline



Beam commissioning

The 2-month timeline breaks down into 3 approximate phases:

1. **Design and Construction** (months 1 to 24)
2. **Installation** (months 25 to 30)
3. **Commissioning** (months 31 to 42)

The first 4 technical milestones have been met **on schedule or early**.


#	NYSERDA milestone	Baseline	Actual	Forecast
	NYSERDA funding start date		31-Oct-16	
1	Engineering design documentation complete	31-Jan-17	31-Jan-17	31-Jan-17
2	Prototype girder assembled	30-Apr-17	30-Apr-17	30-Apr-17
3	Magnet production approved	30-Jun-17	23-Jun-17	30-Jun-17
4	Beam through Main Linac Cryomodule	31-Aug-17	16-Jun-17	31-Aug-17
5	First production hybrid magnet tested	31-Dec-17		31-Dec-17
6	Fractional Arc Test: beam through MLC & girder	30-Apr-18		30-Apr-18
7	Girder production run complete	30-Nov-18		30-Nov-18
8	Final assembly & pre-beam commissioning complete	28-Feb-19		28-Feb-19
9	Single pass beam with factor of 2 energy scan	30-Jun-19		30-Jun-19
10	Single pass beam with energy recovery	31-Oct-19		31-Oct-19
11	Four pass beam with energy recovery (low current)	31-Dec-19		31-Dec-19
12	Project complete	30-Apr-20		30-Apr-20

Go/
no-go




Go/no-go 2

Name
CBETA
PROJECT MANAGEMENT
Milestones
FY2017
Milestone (T-1): NYSDA Funding Date Start (Actual 10/31/2016)
Milestone (T-1): Engineering Documentation Complete
Milestone (T-1): Prototype Girder Assembled
Milestone (T-1): Magnet Production Approved
Milestone (T-1): Beam through Main Linac Cryomodule (MLC) [Actual Finish 6/16/17, Planned Finish 8/31/17]
FY2018
Milestone (T-1): First Arc Production Magnet Tested
Milestone (T-1): Fractional Arc Test: Beam through MLC & Protot
FY2019
Milestone (T-1): Girder Production Run Complete
Milestone (T-1): Final Assembly & Pre-Beam Commissioning Corr
Milestone (T-1): Single Pass Beam Energy Scan
FY2020
Milestone (T-1): Single Pass Beam with Energy Recovery
Milestone (T-1): Four Pass Beam with Energy Recovery (Low Curr
Milestone (T-1): CBETA Commissioned and Project Complete




Fractional Arc Test = go/no-go 2




Injector CryoModule
(ICM) 6 MeV


Beam dump

Go/no-go milestone 1






Go/no-go milestone 2: **MUST DO ON TIME !**



Push toward 4-pass ERL operation until April 2020

Project management



WBS		WBS/System Name	Funding (\$M)	BNL Total (\$M)	CU Total (\$M)
A1.01		PROJECT MANAGEMENT	3.4	2.0	1.4
A1.02		ACCELERATOR DESIGN	1.3	0.2	1.1
A1.03		DC GUN/INJECTOR	0.6	-	0.6
A1.04		RF SYSTEMS & CRYOGENICS	2.8	-	2.8
A1.05		FFAG MAGNETS & GIRDERS	4.4	4.4	-
A1.06		SPLITTER	2.0	-	2.0
A1.07		POWER SUPPLIES	0.9	-	0.9
A1.08		CONTROLS	0.8	0.2	0.6
A1.09		INSTRUMENTATION	2.0	1.2	0.8
A1.10		VACUUM & BEAM STOP	1.3	-	1.3
A1.11		SYSTEM INTEGRATION	3.5	-	3.5
A1.12		BEAM COMMISSIONING	1.2	-	1.2
A1.13		SAFETY	0.8	-	0.8
TOTALS		CBETA	25.0	8.0	17.0

The BNL/CU total split is **\$8.0M / \$17.0M** (includes labor).

PM, AP, Instrumentation, Beam Commissioning: **collaborative**.

The other WBS activities are mostly – or completely – the responsibility of one partner or the other.

At **Cornell**, almost all procurements have been issued: RF amplifiers, vacuum pump skids, splitter magnets, vacuum pumps, vacuum gate valves, and power supplies.


- The largest outstanding construction cost is for **two penetrations in the east wall** of the experimental hall.


At **BNL**, **Halbach magnets and girders** are being purchased through four major procurements: permanent magnet material, magnet assembly, dipole correctors, & girder plates.

- Halbach magnet & girder costs will be **accurately known** when all bids are received, around **December 2017**.

Very strong focusing

As in EMMA, **displaced quadrupoles** in arc FODO cells act as “combined function magnets”







Periodic orbits at 4 design energies — 42, 78, 114, 150 MeV — are displaced over about 50 mm

Short magnets, large apertures: field maps !


“Long” drifts (12 cm) for Beam Position Monitors et cetera.

FODO cell stability
limits energy range




Tunes at 4 discrete energies
must avoid resonance lines !

Almost no layout symmetry




Parameters (drift length, angle, dipole component, **offsets** ...) follow an **adiabatic function** in the transitions




Straight

Arc


Transition



Return arc optics



Linac & splitter optics




Halbach magnets


Halbach (permanent) magnets




Permanent
magnet
blocks



$k=2$



$k=3$




Alignment pins for repeatable Halbach assembly

Halbach permanent magnet **quadrupoles with offset centers**: multiple styles of combined function magnets.

Design questions, physics vs engineering:

Q1: How many different magnet styles?

Q2: How many girder styles?



Magnets styles & girders

Halbach Styles (S. Berg, S. Brooks)

Style name	Length m	Int B.dl T.m	Int G.dl T	Radial aperture mm
QF	0.133	0.00000	-1.5378	43.1
BD	0.122	-0.03759	1.3600	40.1
BDT1	0.122	-0.01223	1.3600	49.085
BDT2	0.122	-0.03102	1.3600	44.938
QD	0.122	0.00000	1.3595	40.1
QFH	0.0665	0.00000	-0.7692	43.1
BDH	0.061	-0.01881	0.6804	40.1

171113

Girder	QF	BD	BDT2	BDT1	QD	QFH	BDH
GFA1	4	4					1
GFX	4	4					
GFX	4	4					
GFX	4	4					
GTA1	4		4				
GTA2	4		4				
GTA3	4		2	2			
GTA4	4			4			
GTA5	4			4			
GTA6	4			4			
GZX	4				4		
GZX	4				4		
GZX	4				4		
GZ1	3				3		
GZX	4				4		
GZX	4				4		
GZX	4				4		
GTB1	4			4			
GTB2	4			4			
GTB3	4			4			
GTB4	4		2	2			
GTB5	4		4				
GTB6	4		4				
GFX	4	4					
GFX	4	4					
GFX	4	4					
GFB1	4	4				1	1
	107	32	20	28	27	1	1

A: 7 magnet styles


QFH & BDH are half length one-offs.

8 magnets per girder,
with an evolving mix
(Note broken symmetry!)

Magnet & girder construction



Pre-production girder (April 2017)






FARO arm
(survey)

Magnet with
corrector


Rotating coil
(field quality)

Rotating coil test stand




Green ring holds variable length iron tuning wires for harmonic reduction — “tuning”

Iron wire field quality tuning




Splitters




Splitters enable **individual control of 4 beams**, with tunable electro-magnets.

“**Common**” magnets are ordered, **septum magnets** are in design.

Common magnets & septa




Adjustable path lengths




Adjustable path lengths on enable energy recovery with
1, 2, 3, or 4 acceleration (and deceleration) passes

Changing configurations is time consuming ...




$$T_1 \cdot f_{\text{rf}} = 343 - 0.5$$



Harmonics:

$$T_2 \cdot f_{\text{rf}} = 343 - 0.5$$


$$T_1 \cdot f_{\text{rf}} = 343$$



Harmonics: $T_3 \cdot f_{\text{rf}} = 343 - 0.5$

$T_2 \cdot f_{\text{rf}} = 343$

$T_1 \cdot f_{\text{rf}} = 343$




$$T_4 \cdot f_{\text{rf}} = 343 + 1.5$$

Harmonics: $T_3 \cdot f_{\text{rf}} = 343$


$$T_2 \cdot f_{\text{rf}} = 343$$

$$T_1 \cdot f_{\text{rf}} = 343$$

Fractional Arc Test configuration



Holes-in-the-wall



Holes are being cut in the east concrete wall for the beam stop & first arc girder.

There are **geometric challenges** to squeezing a 70.1 m circumference machine into L0E.

Implications for future flexibility & upgrades!



Nov 30, 2017

Holes-in-the-wall (2)



Beam stop penetration

December 6: The wall has not fallen down, so far.

Top ten:

1. **Halbach magnets:** schedule slip would delay CBETA.
2. **Main Linac & Injection CryoModules:** complex to repair
3. **DC gun:** like MLC & ICM, repairs could take months.
4. **RF amplifiers: schedule,** custom built, infant mortality.
5. **East wall penetrations:** tight schedule for FAT.
6. **Splitter magnets:** timely delivery
7. **Beam halo & losses:** additional shielding costs
8. **Magnetic field fluctuations:** e.g. power supply ripple
9. **Septum magnets, power supplies:** technical challenge
10. **Key staff loss & availability:** limited resources.

After NYSERDA: expanded collaboration


An ERL is necessary for beam-cooling, to reach the highest EIC luminosities in any scenario:

- JLEIC or eRHIC,
- ring-ring or linac-ring
- conventional or coherent electron cooling

CBETA is a prime platform for Strong Electron Cooling R&D (see presentations by Benson, Douglas & Zhang at <https://www.bnl.gov/eiccm2017/>)

CBETA can also be considered to be a high current RF cryomodule test stand (eg 650 MHz cavities for eRHIC).

ERL landscape (Douglas)



Dave Douglas:

What we have (Mosquito) ... vs ... what we need (F-22 Raptor)



Stealth by wood & canvas or by composites?

Parameter	Unit	State-of-the-art	CBETA	Required
Bunch charge	nC	0.1	0.125	3
Beam current	A	0.01	0.04	0.1 to 1.0
Beam power	MW	1	6	10 to 100
Rep. rate	MHz		31 to 325	43.3

Although there is a **long way to go** to practical parameters, **many** high bunch current, beam quality & optics **issues** can be **addressed** in the **configuration as-built by NYSERDA**:

1. **microbunching,**
2. **coherent synchrotron radiation,**
3. **space charge,**
4. **higher order modes,**
5. **beam break-up, ...**

1. High current effects

- a) Space charge
- b) Halo dynamics**
- c) HOM heating
- d) Intra-Beam Scattering
- e) Touschek scattering
- f) Gas scattering
- g) Ion accumulation

2. Beam quality

- a) Emittance matching
- b) Time-of-flight control**
- c) Wakefield interactions
- d) Micro-bunching instability
- e) Coherent Synch. Radiation**

3. Transport of damaged beam

- a) Phase space rotation
- b) Large 6-D phase-space optics

4. Recovery topics

- a) Energy spread growth during deceleration.
- b) Transverse halo growth during deceleration.
- c) Recirculative Beam Breakup**
- d) Ion instabilities
- e) Simultaneous control of multiple beams**

DarkLight – an experiment to find dark matter particles

Compact **Compton backscattering** for hard x-rays

THz laser – complementing CHESS

Beam for time-resolved **electron diffraction** from 1 to 6 MeV

Beam for **Plasma Wakefield Acceleration**

ASML medical isotope **cavity testing** with beam

Preparations for **PERLE** & LHeC

Permanent magnet & **very strong focusing optics test bed**

1. **NYSERDA funding** **Construct** a high performance CBETA, commission to **modest KPPs**, e.g. 1 mA.
 - opportunities for participation in commissioning
2. **DOE Nuclear Physics funding ?** **EIC R&D @ CBETA**
commissioning towards ultimate parameters, e.g. 40 mA.
 - BNL + Cornell + **JLab** + ...
3. **?? funding** **Add a high energy CBETA beamline(s)**
for cooling &/or other experiments & applications
 - e.g. **DarkLight** (MIT) proposal, ...
4. **“Zero” funding?** **Networking** on common physics and engineering topics. **ARIES?**
 - bERLinPro, MESA, PERLE, UK-XFEL, ...

Summary

The project is **29% complete** (out of 3.5 years & \$25M)

“Risks could occur at any time”, but **consider next steps** in commissioning a **state-of-the-art** ERL:

1. **4 pass** up, 4 pass down
2. **Superconducting RF** (1.3 GHz)
3. **Very strong focusing** single aperture optics
4. Halbach **permanent magnet** return arc

Next: perform challenging R&D with world-beating performance **without additional capital expenditures**

Capital expenditures, later, would enable much more, e.g. high-energy beamline, EIC cavity prototyping, etc.

We (BNL & Cornell) seek **DIRECT collaboration** in CBETA:

- individual beam commissioners in 2018
- students & post-docs
- JLab on EIC R&D
- potential “users” e.g. MIT

We also seek enhanced **INDIRECT collaboration** on topics of mutual interest with other ERL projects:

- bERLinPro, MESA, PERLE, UK-XFEL ...

Technical Milestone

2017

Dec 19

Oversight Board meeting

Dec 31

5

"First arc production magnet tested"

2018

Jan 15-17

PERLE collaboration meeting, Daresbury

Feb 12

Shift training begins (Bartnik)

Feb 12

Dario Pellegrini arrives at CU

Feb NN ?

FAT shifts begin

Feb 22-23

Advisory Committee meeting, CU

Mar NN ?

Cost, schedule & management review, BNL

April 30

6

"Fractional Arc Test"

Nov 30

7

"Girder production run complete"

Backup slides

History of ERLs (Dave Douglas)

Tigner (1965)



BAF FET (early 1990s)



ONR INP (2012)



Chalk River
(1970s)



IR Demo (late 1990s)



Industrial EUV Driver (2012)



LANL SDI (early 1980s)



Upgrade (Early 2000s)



JLEIC CCR



HEPL (mid-late 1980s)



JLAMP (ca 2010)



ONR MW FEL



CERN Courier article

Advisory Committee topics

Wencan slides

Adam slides