


# Introduction to the Cold Powering Project for HL-LHC

A. Ballarino Leader of WP6a (Cold Powering) CERN, 20/06/2018




## The project









## The HL-LHC Tunnel



#### **LHC Tunnel and equipment Cryostat and leads Cryostat and leads** Power converters **DFHX DFHM** Power converters VALVES BOX **SC** Link for **Triplets** ≈ 100 m **SC** Link for **Matching Sections** ≈ 130 m **SCLINK** 120<Ø< 200 D1 **DFX Cryostat D2 (DFM)** (connection to magnets bus-bar) **Cryostat (connection to magnets bus-bar)**

## **LHC Tunnel Configuration**





## Requirements for the powering of the Triplets

Trim Q1a (35 A)  $\rightarrow$  Local powering

EDMS N. 1821907

	Magnet	Cold Powering			
	I <sub>ult</sub> (kA)	I <sub>peak</sub> (kA)	I <sub>lead</sub> (kA)	I <sub>cable</sub> (kA)	N <sub>leads</sub> /N <sub>cables</sub>
MQXF	17.82	-	18	18	2
Trim Q1	2	2.4	2*	7	1
Q2a/Q2b	Protec.	5.6	2*	7	1
Trim Q3	2	6.8	2*	7	1
MCBXFB	1.73	-	2	2	2+2
MCBXFB	1.59	-	2	2	2+2
MCBXFA	1.73	-	2	2	2
MCBXFA	1.59	-	2	2	2
MQSXF	0.2	-	0.2	0.2	2
MCSXF/MCSSXF	0.12	-	0.12	0.12	2+2
MCOXF/MCOSXF	0.12	-	0.12	0.12	2+2
MCDXF/MCDSXF	0.12	-	0.12	0.12	2+2
MCTXF/MCTSXF	0.12	-	0.12	0.12	2+2
D1	12.96	-	18	18	2





<sup>\*</sup> Able to cope with over-currents without excessive over-heating

## Requirements for the powering of the Triplets

#### Number and type of components per system

Rating (kA)	N <sub>leads</sub>	N <sub>Cables</sub>
18	4	4
7	-	3
2	12+3*	12
0.2	2	2
0.12	16	16
Total	37	37

Leads rated at 0.12 kA and 0.2 kA (18 in total) proposed for local powering (as in the LHC)


Updated in order to take into account recent changes on the magnets circuits (HL-LHC Magnets Circuits Internal Review, EDMS N. 1807471, May 2017)





EDMS N. 1821907

# **DFH - Concept**








## **Development activity at CERN**

Test station operational from 2014 until end 2016 – now being upgraded






# **Industrial procurement of long cryostats**

SC Link cryostats @ CERN









## **R&D Development**


#### SC Link

- MgB<sub>2</sub> wire: developed with industry. Being procured
- MgB<sub>2</sub> cable: prototyping on-going in industry
- HTS Current leads
  - Prototypes at CERN (internal design/construction)
- DFX
  - Small scale demonstrator being constructed
- DFH
  - Clear baseline changed in 2018 for simplifying cooling






### **DFH Functionalities**




# **DFH Integration in the tunnel**







#### **HL-LHC Timeline**



Integration in LHC Tunnel in 2024

All large procurements of WP6a components launched in 2018 and 2019





# Looking forward to starting the collaboration

Questions?



