



# 3<sup>rd</sup> International Workshop on Superconducting Magnet Test Stands



Uppsala - Sweden  
2019, June 11 – 12  
Ångström laboratory



## SM18 CRYO UPGRADE

Nicolas GUILLOTIN (CERN)  
on behalf of TE-CRG

And major contribution of : F. DHALLA, J-P. LAMBOY, R. LAMY, , J. MOULEYRE, A. PERIN, M. PEZZETTI,



# OUTLOOK

**I** INTRODUCTION & CONTEXT

**II** SM18 SIMPLIFIED CRYO DEVICES : BEFORE & AFTER UPGRADE

**III** KEY FIGURES



**IV** UPGRADE HANDOVER & RESTART PROTOCOL

**V** OVERVIEW

## SM18 : CERN main facility for testing SC accelerator magnets and SC RF cavities

SM18 cryo infrastructure is being significantly upgraded (starting in 2019) to meet requirements for :

- **LHC High Luminosity project (HL LHC)**
- **R&D program for SC magnets**
- **RF equipment until 2023 and beyond**



## SOME OF THE SYSTEMS CURRENTLY IN OPERATION IN SM18

- **5 vertical magnet cryostats :**  
HFM, CLUSTER D, SIEGTAL,  
LONG, DIODES (80K, 4.5 K, 1.9 K)
- **10 Horizontal test benches  
for magnets** (80K, 4.5 K, 1.9 K)
- **1 test bench for SC Link :**  
(30 - 4.5 K, 2 ~ 15g/s)
- **4 test benches for RF  
cavities :** V3, V4, V5, V6  
(4.5 K, 1.9 K)
- **2 test benches for  
Cryomodules :** M7, M9  
(80K, 4.5 K, 1.9 K)
- **1 independent test Bench :**  
Eu HIT GReC (10 - 4.5K)



Vertical magnet tests



Hor. Magn, feed box



Horizontal magnets test benches



SC links tests



RF cavities & CM tests



Vertical magnet tests

**In Operation**



# SOME DEVICE OF THE CRYOGENIC INFRASTRUCTURE CURRENTLY IN OPERATION

6kW Linde Cold Box

27g/s (~700L/h)  
@ 4.5K



Purification units

3 x 130 Nm<sup>3</sup>/h  
Burckardt recovery  
compressors +  
2 Purifiers 200 Nm<sup>3</sup>/h  
at 180 bars

Very Low Pressure  
compressors (WPU)

Values per WPU unit :  
6 g/s @ 10 mbar  
12 g/s @ 20 mbar  
18 g/s @ 30 mbar (max)



Cool down -  
warm up unit  
(CWU)

2 x CWU 80g/s –  
2 x 120kW @80K


With 3 Kaesers  
compressors

In Operation

## FACING THE HL LHC PROGRAM

### New SC devices for the HL-LHC project require the SM18 cryostructure upgrade

- 11T dipoles
- Standalone magnets
- SC link  
(Cables & current leads)
- Crab RF cavities
- Inner Triplet magnets



Low- $\beta$  magnets - Nb3Sn technology - peak field of 11.4 T  
 With : 2 outer quadrupoles, Q1 & Q3 +  
 a central one divided into 2 identical magnets, Q2a and Q2b

**Project**

HL LHC String will be a new test stand to validate the collective behaviour of a structure including IT magnets

“HL-LHC IT STRING TEST”, M. Bajko,  
 LHC Performance Workshop 2018 Chamonix

**Project**



**I INTRODUCTION & CONTEXT**

**II SM18 SIMPLIFIED CRYO DEVICES : BEFORE & AFTER UPGRADE**

**III KEY FIGURES**

**IV UPGRADE HANDOVER & RESTART PROTOCOL**

**V OVERVIEW**



## REQUIREMENTS FOR THE UPGRADE OF THE CRYOGENICS INFRASTRUCTURE

### BASED ON TEST PROGRAM - ASSUMPTIONS FOR COVERING THE MAIN TEST BENCHES


- Magnet test benches: 2 vertical & 2 horiz. magnets at cold / month with 2 magnets powered simultaneously
- Superconducting cavities: 1 cavity /2 weeks & 1 cryomodule test every 6 months
- Parallel test of a superconducting link (SC Link) and/or the IT string (String)
- Possibility of additional individual systems tests on dedicated facilities



2019 JUNE, 11

# SCHEMATIC LAYOUT OF THE SM18 CRYO INFRASTRUCTURE AFTER UPGRADE

- Infra
- Test benches
- Cold Boxes
- LHe dewar
- GHe stock
- Distribution



2019 JUNE, 11

## SM18 NEW COLD BOX



Mechanical Integration, Electrical and Control System review held at Linde Kryotechnik AG (LKT) in 2018 and beginning of 2019



Transport and arrival at the SM18  
2019 MAY, 14



Cold Box installed in the SM18  
2019 MAY, 15



## SH18 NEW MAYEKAWA COMPRESSOR






## PROCESS UPGRADE FOR Nb3Sn MAGNETS

Nb3Sn SC magnet tests at the SM18 need a control of the  $\Delta T$  during cool down and warm up, in the 80 – 300K range

⇒ **Automated  $\Delta T$  control** during cool down / warm up of Nb3Sn magnets has been implemented and need to be evaluated in real conditions



- Installation of a new **PT100** close to the magnet cold mass
- Measurement of the  $\Delta T$  between CFB Temp\_inlet – CFB Temp\_outlet = value A
- Measurement of the  $\Delta T$  between CFB Temp\_inlet – Magnet new PT100 = value B
- Continuous regulation of the  $\Delta T$  based on the max value : A or B
- Redundancy for the PT100 is necessary
- Particular case for the reconnexion after a trip



## CONTROL & ELECTRIC UPGRADE

For the 35g/s Cold Box & Mayekawa compressor :

- Electrical cabinet installation for the 35g/s CB & Mayekawa CP
- CP logic document sent to LKT, ready to be commissioned
- CB logic sent to LKT



Control & Elec upgrade for the SH18 :

Buffers and Burkhardt controlled by an independent system to allow independent maintenance and debugging

**Done**



2019 : New rack with independent M580 PLC + RIO (Remote I/O)

**Done**

2020 : M580 PLC moved to Infra Cabinet and RIO linked with fiber optic

**2020**



2019 JUNE, 11

**I INTRODUCTION & CONTEXT**

**II SM18 SIMPLIFIED CRYO DEVICES : BEFORE & AFTER UPGRADE**

**III KEY FIGURES**

**IV UPGRADE HANDOVER & RESTART PROTOCOL**

**V OVERVIEW**



2019 JUNE, 11


15

## SM18 CRYOPLANT GENERAL KEY FIGURES : AFTER UPGRADE


System	Characteristics
EXISTING 6kW CB – “LINDE A”	27g/s (~700L/h) @4.5K
<b>NEW Linde CB – “LINDE B”</b>	<b>35g/s (~1000L/h) @4.5K</b>
Process compression station	3 Stal He compressors (350 g/s @19 bar), 1.6 MW elec. power + ORS <b>+ new MAYEKAWA compressor (main drive motor of 1.4 MW)</b>
Very Low Pressure Pumping (WPU)	2 warm pumping units, each one : 6 g/s @ 10 mbar 12 g/s @ 20 mbar 18 g/s @ 30 mbar (max) To each WPU is dedicated a very low pressure heater of 32 kW (20g/s)
Pre-cooling to 80K	2 x CWU (80g/s - 2 x 120kW @80K) - With 3 Kaesers compressors
GHe Purification	5 x 80 m <sup>3</sup> Balloons at 1 bar (3 Burckardt recovery compressors + 2 Purifiers 200 Nm <sup>3</sup> /h at 180 bars)
Pure GHe storage	8 x 75m <sup>3</sup> @18 bars
LHe storage	1 x 25 m <sup>3</sup> LHe storage at 1.6 bar (+ 1x 10 m <sup>3</sup> mobile)
LN2 storage	50'000L Dewar




# LHe CONSUMPTION FOR COOL DOWN TO 4.2K - COOL DOWN DURATION – STEADY STATE



- The 27g/s cold box will be dedicated to the **HL LHC String** and could complement the Dewar for the other test benches



- The new 35g/s cold box will directly and significantly increase the LHe capacity for :



- The cool down

- The steady state

- The Quench recovery

EQUIPMENT	LHe FLOW FOR QUENCH RECOVERY	QUENCH RECOVERY TIME
	[g/s]	[h]
HFM	12	4
Cluster D	12	4
Horizontal dipoles	14	2.25
LONG	6.8	2



**I INTRODUCTION & CONTEXT**

**II SM18 SIMPLIFIED CRYO DEVICES : BEFORE & AFTER UPGRADE**

**III UPGRADE KEY FIGURES**

**IV OPERATIONAL PROTOCOL & TOOLS AFTER THE UPGRADE**

**V OVERVIEW**

# RESTART PROTOCOL : CHECKLISTS

CHECKLIST N°1 : COOLING, WARMING UP, POWERING CHECKLIST -TO BE COMPLETED BEFORE LAUNCHING THE OPERATING PHASE-									
EQUIPMENT NAME (of the Magnet, Cavity, Module)									
TEST BENCH NAME									
DESCRIPTION	Type of Magnet / Cavity : Main dimensions (m): Weight (kg) : Filling pieces -if applicable- (Y/N) : Estimated volume of LHe needed during nominal Operation (m3) :					Inductance -if magnet- : Number of current Leads -if applicable-: Position of the heaters -if applicable-:			
TOPIC	SUB-TOPIC	WHO	YES	NO	VALUES	Date	Remarks	Names	
SAFETY ASPECTS	Nominal pressures clearly defined (Pnom)	USERS							
	Maximal pressures clearly defined (Pmax)	USERS							
	Standard insert -if applicable-	USERS							
	Safety valves & rupture disks validated	USERS & CRG-ME & CONTRACTOR							
	Risk assessment performed	USERS & CRG-ME & CONTRACTOR							
EQUIPMENT PROTECTION	Interlock chain verified : Interlocks and alarms defined and implemented (cryo OK operational)	USERS & CRG							
	Delta_T instruction for cool down/warm up clearly defined -if applicable-	USERS							
	Max/min Helium flow instruction for cool down/warm up clearly defined -if applicable-	USERS							
	Requested flow for temperatures for the current leads -if applicable-	USERS							
FILLING PIECES	Filling pieces available and installed to reduce LHe consumption	USERS							
EQUIPMENT HARDWARE	Hardware ready for Cryo Operation : mechanical & instrumentation	USERS & CRG							
PROCESS & PROCEDURES & ASSOCIATED DOCUMENTS	Automated process needed and operational to operate without a permanent control of Cryo Operators	USERS & CRG							
	Operation procedure for cool down, warm up etc	USERS & CRG							
	P&ID of the Cryo Equipment	USERS & CRG							
	Electrical schemes for cryogenics	USERS & CRG							
	Existing prior Cryo report	CRG							
Existing prior USERS report	USERS								
ORGANISATIONNAL ASPECTS	Contacts clearly defined for the CRYO follow up	CRG							
	Contacts clearly defined for follow up by the USERS	USERS							
	Test sequence : Target of the tests - including evaluation of tests duration	USERS							
	Need to work outside standard operating hours (notice period to be defined with the Contractor)	USERS & CRG							
OK FOR A REQUEST FROM USERS TO CRYO									

SAFETY


ORGANIZATION

OPIMIZATION & TOOLS

COMMUNICATION



Could be implemented with CARPENTER






## OPERATIONAL PROTOCOLS

### SAFETY

- Human safety  $\Rightarrow$  respect of rules and best practices for Operation
- Equipment safety  $\Rightarrow$  preventive maintenance, follow up with INFOR

### ORGANIZATION



### OPIMIZATION & TOOLS

- Excel forecast tool to anticipate and simulate LHe consumptions

### COMMUNICATION

- “Weekly” general Coordination meetings for the tests (priority definitions)
- Weekly Technical meetings
- Reports on activities



## SUMMARY

**The upgrade of the cryogenic system at the SM18 gives the possibility to :**

- Increase **the global LHe capacity** for the Magnets and RF cavity tests
- Ease **Quenches recovery** for Magnet tests
- Allow the operation of the SM18 test benches while also running the test program of the HL-LHC String
- Allow one CB/Compressor system to be under maintenance while the LHe supply to dewar can continue  
⇒ **Operation flexibility & Redudancy in case of major issue**

