



WP6a DFH Cryostats

DFH manufacturing & assembly options

Paul Cruikshank, Amalia Ballarino

14 February 2020

Recall


- DFH fundamental design change (single cryostat) - Q3 '19
- Conceptual Design Review - Nov '19
- UU/RFR visit to Cern - Mid Dec '19
- Cern brainstorming on manufacturing options - Jan '20

UU Collaboration with Industrial partner

- Baseline Objectives:
 - Produce 5 DFHX & 5 DFHM cryostats according to Cern design.
 - Disassemble cryostats for delivery to Cern*
- Comments
 - Unit #1 of each type will be an operational spare.
 - Supply of DFHX #1 and its subsequent re-assembly with SC cables by Cern provides the go ahead for DFH series manufacture.
 - RFR wishes to strengthen it's competencies in cryostat technologies.

*as cables of the superconducting link and HTS current leads can only be integrated at Cern, the DFH cryostats must undergo final assembly by Cern.

DFHx sub-components



DFHx cryostat cannot be fully assembled (welded) without the MgB2 cable and current leads:
 ⇒ At RFR, assemble & cut welds or assemble without welding & demonstrate that parts fit together.
 ⇒ Final assembly & test at Cern (Cern responsibility)

Uppsala Collaboration Hardware Deliverables




Uppsala & RFR visit 10/12/2019

- Cern design development according to Nov'19 CDR plan
 - 3D design + integration by end Jan ✓
 - Calculations + detail design by end March + PRR **on-going**
- UU & RFR cryostat production
 - RFR request 12 months manufacturing (wrt 9 month allocation in baseline)
 - Plus, need several additional wks prior to RFR manufacture start
 - RFR review of design dossier
 - RFR make price offer to UU based on Cern specification drgs
 - UU sign contract with RFR
 - UU sign collaboration agreement with Cern
- Technical
 - If DFH assembled at RFR (welding, assy, MLI, leak test, p.test, etc) it implies re-cutting prior to delivery.
 - If DFH not assembled at RFR, learning goals are difficult to achieve

DFHX #1 planning

Dates coherent with WP6a global planning

	2019	2020				2021				2022				2023					
	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4		
DFHx #1	Design development	Cryostat Manufacturing (Upp)				Assy Cern	ProtoTest					String Assembly				String Test			
DFx #1	Detail drg	Cryostat Manufacturing (SOTON)																	
DSHx #1	MgB2 cable & Link Cryostat Manufacturing																		



end date ?

DFHm #1,2,3,4,5		Design development		Series OK	#1	#2	#3	#4	#5		
DFHx #2,3,4,5				Series OK	#2	#3	#4	#5			

- DFHX #1 delay ~ 5 months wrt to baseline
- DFHX #1 delay doesn't impact String planning
- DFHX #1 delay impacts the early testing of the DSHX link proto & current leads
- DFHX #1 delay impacts the start date for DFH series production & UU collaboration end date



manu* = manufacture, assemble, l.test, p.test, disassemble

DFH manu & assy options, 14 February 2020

DFH Manufacturing

- How to fit in the baseline planning ?
- How to collaborate most effectively ?

DFH Manufacturing & Assembly Options

Options	@ Sweden	@ Cern
Baseline	Components+assembly+test+disassembly	Assembly with CL & SC cables (Cern only)
Variant 1	Components+partial assembly	Assembly with CL & SC cables (Cern only)
Variant 2	Components	Assembly with CL & SC cables (Cern with UU/RFR)

DFH manu & assembly options

Approach	Advantages	Disadvantages
Baseline – DFH cryostat components are manufactured, fully assembled and tested by ind partner (without SC cabling), then disassembled (cut helium vessel welds) prior to delivery to cern. DFH, CL & link assembled by Cern.	<p>Validation of mechanical assy, I.test, p. test, CE marking.</p> <p>Ind partner builds cryostat with KT from cern.</p>	<p>Deformations due to welding & cutting may hinder assy at cern.</p> <p>Manpower loss: p.test, I.test, CE cert, assy/dis-assy.</p> <p>Assy confirmation in industry doesn't consider cable integration.</p>
Variant 1 – DFH cryostat components manufactured and partially assembled by ind. partner without full welding of helium vessel (without SC cabling), then disassembled prior to delivery to cern. DFH, CL & link assembled by Cern.	<p>Welding/cutting eliminated.</p> <p>Minor assy in industry, so reduced manpower.</p>	<p>No I.test or p.test on helium vessel.</p> <p>No CE marking.</p> <p>Manpower loss: assy/disassy.</p> <p>Assy validation incomplete.</p> <p>KT for ind partner is limited.</p>
Variant 2 – DFH cryostat components manufactured by ind. partner then assembled and tested at cern with simultaneous SC cable integration. DFH, CL & link assembled by Cern, UU & RFR.	<p>Disassembly/cutting eliminated</p> <p>Assy considers SC cable integration.</p> <p>Assy execution, optimisation & issues (including reworking) resolved by cern/UU/ind partner together.</p> <p>Max KT opportunity for industrial partner.</p>	<p>Increased assembly resources required at cern.</p>

Assemblability validation of UU/RFR supply

Approach	Validation objective	Vacuum vessel	Helium vessel	Internal supports	Assy tooling	Comments
Baseline	Cryostat assemblability	✓	✓	✓	✓	Cryostat is assembled with neither CL nor SC link so constraints during final assembly sequence at Cern are not evident
	Link & CL assemblability*	✓	✗	✗	✗	
Variant 1	Cryostat assemblability	✓	✗	✗	✗	Vacuum chamber can be assembled on external supports. Assy checks on components can be made to validate machining tolerances but assy sequence can't be performed.
	Link & CL assemblability*	✓	✗	✗	✗	
Variant 2	Cryostat assemblability	✓	✓	✓	✓	Assy sequence with link and current leads can be validated/optimised
	Link & CL assemblability*	✓	✓	✓	✓	

*mechanical interfaces to cryostat, routing of SC cables, splice execution, routing of instrumentation cabling.

DFHX #1 Knowledge Transfer Opportunities – Variant 2

KT Opportunity	Vacuum vessel	Helium vessel	Internal supports	External Supports	Multi-layer insulation	Cryostat Assembly
Material choice	Green	Yellow	Green	Light Blue	Green	Light Blue
Component manu	Green	White	Green	KT@RFR	Green	Light Blue
Welding	Light Blue	Light Blue	Light Blue	Light Blue	Light Blue	Yellow
Cleaning	Green	Green	Green	Light Blue	Light Blue	Green
HV assembly	Green	Green	Light Blue	Light Blue	Green	Green
Sealing tech	Green	White	Light Blue	Light Blue	Light Blue	Green
Instrumentation	Light Blue	Light Blue	Light Blue	Light Blue	Light Blue	Green
Pumping	Green	Green	Light Blue	Light Blue	Green	Green
Leak testing	Green	Green	KT@RFR	Light Blue	Green	Green
Pressure test	Light Blue	Yellow	Light Blue	Light Blue	KT@cern	Green

3-4 months assembly duration,
RFR % presence/timing to be agreed,
Component delivery sets start date

Planning Optimisation

- Consider strategy for DFHX #1 ≠ DFH series
- @UU/RFR
 - Baseline scope = components+assy+test+disassy
 - Variant 2 scope = components
- @Cern
 - Baseline design change/reworking = transport Cern/RFR/Cern
 - Variant 2 design change/reworking = Cern workshops
- Comments
 - Cern design is based on Cern assembly methods & existing tooling
 - Variant 2 - RFR can built-to-print with higher confidence
 - Variant 2 - knowledge transfer easier to integrate

⇒ RFR manufacturing duration in Sweden reduced with Variant 2 ?

DFH baseline & variants summary


- **Baseline**
 - Provides validation of cryostat assemblability in industry with the risk that SC cable integration difficulties can be found quite late at cern, requiring reworking of the supply.
 - Manpower to assemble and test the cryostat in industry is lost due to the obligation to reopen the helium vessel.
- **Variant 1**
 - Provides a cost effective approach for series production with a validated solution
 - Manpower resource needs are lower in industry but higher at cern.
- **Variant 2**
 - Provides validation of cryostat assemblability, plus validation of SC link and current lead assemblability.
 - Brings together Cern, Uppsala and RFR during the assembly phase, facilitating execution/problem solving/optimization/learning.
 - Provides an effective approach for start-of-series production eg DFHX #1 & DFHM #1.

DFH proposal


- Propose Variant 2 for production of DFHX #1 & DFHM #1
- Propose Variant 1 or Variant 2 for production of DFH series, with RFR assistance at Cern.
- Explore how UU, RFR and Cern can drive the component and assembly works, ensuring timely assembly of DFHX #1 at Cern in early 2021 (with CL and SC link),.....and providing maximum opportunities for knowledge transfer.

Thanks for your attention !

Spare Slides




PH 10



PH 20

PH 30



12
M